



## BRUNUS ENTERPRISES LTD.

45 Charity Road,  
New Oko Oba, Agege,  
P. O. Box 2187, Ikeja,  
Lagos, Nigeria.

Phone: 08037209102

### PROFORMA INVOICE

#### QUOTATION FOR THE FABRICATION AND INSTALLATION OF GARRI PROCESSING PLANT OF 1TON/DAY

1. Stainless steel cassava grater of 1 ton/hr with;
  - i. 10 Hp motor
  - ii. U-Channel frame
  - iii. 3mm stainless Steel housing ₦700,000
  
2. Mechanical press/fermentation rack with;
  - i. 3 tons mechanical jack
  - ii. U-channel /H beam frame ₦500,000
  
3. Stainless steel frying pot with;-
  - i. Stainless steel material (inner) 3mm
  - ii. Mild steel material for the outer body
  - iii. Insulating material with fibre glass
  - i. U-channel frame ₦900,000
  
4. Medium Size Hammer for milling  
dried garri into fine particles ₦700,000
  
5. Installation cost:- ₦550,000

TOTAL

₦3,350,000

## TERMS AND CONDITIONS OF PURCHASE

### **PAYMENT:**

75 percent of the total cost will be paid before production of the machines can start, Another 15 percent of the total cost will be paid at the completion of the production before delivery to the factory site. The remaining 10% will be paid after delivery, installation and test run.

**DELIVERY PERIOD:** Delivery of the machine shall be 12 weeks from the payment of the 75 percent and the clearing of the cheque. Delivery cost will be borne by the client.

**INSTALLATION OF THE MACHINES:** Five technicians will accompany the plant for the installation and it will take about two weeks once electricity, water and other ancillaries are in place. You will be responsible for the boarding, feeding and transportation of these technicians. The technicians will help you to construct the sedimentation tank if it is necessary.

**TEST RUN:** Five tons of raw cassava tubers shall be required for the test run and it will be provided by you.

**TRAINING:** There is no extra cost for training your workers. You should have your electrician, welder, machine operators and technicians participate in the installation and test run, so that they will be trained on the spot.

**WARRANTIES:** 6 months for any production problem excluding changeable parts affected by aging, misuse and accident. The machines are robust, tested, rugged, resilient and very adaptable to rough and humid African conditions. All the parts that have contact with cassava are made of stainless steel to ensure quality and excellence. The machines will last for a long time once they are maintained twice a year by changing the bearings.

**TECHNICAL SUPPORT:** We will give technical support such as supply of spare parts like the bearings, maintenance of the machines, quality control to ensure the product meets the required standard and specifications. We will also help in the export market through consultancy and brokerage.

**VALIDITY:** The quotation is valid for 90 days from the date of submission after which the price may change.

**DURATION OF CONSTRUCTION:** 12 weeks from the date of advance payment

**GUARANTEE:** All the equipment will be guaranteed for six months from date of installation.